

COORG DIVISION.

[ADVERTISEMENT]

Notification, dated 8th August 1895.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Coorg Division, up to 15th September 1895. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1896.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Mercara between the hours of 11 to 5.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement (in the form given below) showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed, "Tender for construction of Taluk Cutcherry at Somwarpet, North Coorg," in default of which tenders will be rejected.

5. Within fifteen days of the acceptance of the tender, the successful competitor will be required to execute a contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

6. The name of the successful competitor, whose tender has been accepted, will be intimated to him by post. No enquiries regarding the acceptance or rejection of a tender need be made meanwhile.

7. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

CONSTRUCTION OF A TALUK CUTCHERRY AT SOMWARPET, NORTH COORG.

<i>Description of work.</i>	<i>Unit of work.</i>	<i>Approximate quantity.</i>
Earthwork-excavating foundation	C. ft.	6,045
Ditto filling in basement	Do	7,970
Concrete with lime	Do	4,274
Burnt stone in lime	Do	6,110
Brick in lime	Do	17,379
Brick in clay	Do	3,312
Arch-work brick in lime	Do	1,948
Stone slabs	Do	52
Plastering with chunam	S. ft.	27,938
Painting ditto	S. ft.	7,485
Flooring with concrete	S. ft.	5,793
Ornamental cornice work	R. ft.	410
Plain cornice work	R. ft.	1,696
String course	R. ft.	265
Whitewashing	S. ft.	27,933
Colorwashing	S. ft.	7,485
Teak wood work	C. ft.	915
Terrace roofing with 3 course of flat tiles 1½" concrete 1½" cement	S. ft.	1,934
Iron works	Lbs.	184
Zinc flashing	Lbs.	271
Roofing with Mangalore tiles	S. ft.	7,022
Ridging with Mangalore tiles	R. ft.	331
Doors ½ pannelled and ¾ glazed	S. ft.	1,238
Windows ¾ pannelled and ¾ glazed	S. ft.	110
Ditto iron barred and glazed	S. ft.	24
Painting	S. ft.	2,742

Notice, dated, Mercara, 10th August 1895.

Tenders are invited for the supply of burnt stone slabs between 148th mile and 160th mile of the Bangalore-Cannanore road, No.—450 × 6 feet long 1½ feet wide and 6 to 8 inches thick. Tenders will be received up to the 15th September 1895.

For further particulars apply to Mr. N. Leavers, Officer in charge No. III Sub-Division, Virajendrapet, Coorg.

M. LESLIE,
Executive Engineer.